



E. Tallmadge Avenue Widening (SR 261)

PID: 77198

Project Name: Tallmadge Avenue Widening

Project Description: This project consists of total pavement replacement and minor widening of 0.52 miles of East Tallmadge Avenue (SR 261) from the Gorge Boulevard intersection to the Home Avenue intersection. The project will widen the travel lanes to standard 12-foot lanes including new asphalt pavement, concrete curb, concrete sidewalk, and concrete drive aprons. Traffic signalization will be upgraded to pole and mast arm-mounted vehicle and pedestrian signals, fully-actuated signalization process with video surveillance detection, emergency vehicle priority preemption, and interconnected. A 36" water main will be replaced the entire length of the project. Post top LED street lighting will be installed the entire length of the project. Street trees will be installed.

Project Coordinator: Karen Dyer

Work to Begin: Fall 2010

Estimated Completion: Fall 2011

Federal Investment: \$4,530,733

Total Project Cost: \$6,926,149